

**RENOVATIONS TO TIERRA BLANCA
ELEMENTARY SCHOOL - HEREFORD ISD
HEREFORD, TEXAS**

BSA Consulting Engineers, PLLC
Texas Firm Registration No. F-4415
BSA Project No. 2017-104



ADDENDUM TWO

May 7, 2018

NOTICE TO BIDDERS:

The following shall be incorporated in and become a part of the original Drawings and Specifications of the above identified project. Please acknowledge receipt of this Addendum by noting it on your Proposal.

Electrical Items:

- Item 1: On the drawings, Sheet E8, at all exterior building entrance door locations provide a weatherproof J-box at 48" AFF to serve security system card reader device by Owner. Stub a 3/4" conduit from J-box stubbed up to 6" above an accessible ceiling. Verify exact J-box mounting locations with Architect/Owner prior to rough-in.
- Item 2: In the specifications, delete Section 16723 - School Intercom & Program Equipment in its entirety. Contractor shall provide in his base bid an allowance of \$100,000 (one hundred thousand) for the School Intercom & Program Equipment. All J-box and conduit rough-ins indicated on the drawings shall still be included in contractor's bid price and shall not be part of this allowance.

End of BSA Addendum