

AMARILLO EDC - LEASE BUILDING PROJECT

AMARILLO, TX



Amarillo EDC - Lease Building Project

Location: Amarillo, TX

Construction Type:

Warehouse / Industrial

Construction Methods:

Structural members include reinforced concrete piers, reinforced concrete slabs, reinforced concrete tilt-wall panels, and fabricated structural steel. Membrane roofing was utilized for the roofing system. The exterior walls are painted concrete tilt-walls and exterior insulated finish system (EIFS).

Square Footage:

Building: 50,260 s.f.

Contract Amount:

\$5,600,000 (CM @ Risk)

Schedule/Duration:

10 Months

Additional Notes:

Concrete tilt-wall panels just shy of 50' high, weighing nearly 100,000 lbs. each. Southwest General Contractors self-performed the concrete scope of work on this project. Southwest General Contractors completed project on time and under budget.

Southwest
GENERAL CONTRACTORS